



**KENT COUNTY DRAIN COMMISSIONER  
TROY WITH MOSHER & FARNHAM DRAIN**

**NOTICE OF LETTING**

**DATE:** Friday, April 16, 2021  
**TIME:** 10 a.m.  
**LOCATION:** Kent County Road Commission Building  
1500 Scribner Ave NW, Grand Rapids, Michigan 49504  
**QUESTIONS:** (616) 632-7910

The Kent County Drain Commissioner will meet on the above date, time and location to receive construction bids for the Troy with Mosher & Farnham Drain. Bids will then be opened and publicly announced.

The Troy with Mosher & Farnham Drain project will be let in two (2) section(s) as follows, each section having the length, average depth and width as set forth:

***Division I of the Troy With Mosher & Farnham Drain is approximately 1.41 miles and is comprised of open channel, with an average depth of 14-feet and average bottom width of 3-feet. The following items will be required and a contract let for the same:***

**Open Channel Drain Construction**

1	LS	Mobilization
1	LS	Traffic Control
1	LS	Utility Coordination & Protection
6,166	LF	Clearing, Grubbing and Snagging
5,113	LF	Sediment Removal – 3' Bottom Width
1,903	LF	Sediment Removal – 2' Bottom Width
1,350	LF	Spoil Hauling
7,016	LF	Open Channel Seeding

**Drain Crossings**

- Station 22+40, Private Crossing  
Place 30 LF 83" x 128" CMP Arch
- Station 24+80, Private Crossing  
Place 30 LF 83" x 128" CMP Arch
- Station 29+35, Private Crossing  
Place 40 LF 83" x 128" CMP Arch
- Station 37+25, Compass Trail (Paved)  
Clean Existing Culvert
- Station 48+40, Paul Henry Thornapple Trail (Paved)  
Place 60 LF 59" x 81" CMP Arch
- Station 52+20, Private Crossing  
Place 25 LF 59" x 81" CMP Arch
- Station 57+00, Private Crossing  
Place 25 LF 59" x 81" CMP Arch
- Station 207+25, Private Crossing  
Place 25 LF 38" x 57" CMP Arch

**Soil Erosion and Sedimentation Control**

1	LS	Soil Erosion and Sedimentation Control
2	EA	Armored Spillway

7	EA	Outfall Stabilization
600	SY	Riprap End Treatment, MDOT Plain
1	EA	Trail Restoration
4	EA	Private Crossing Restoration
1	EA	Driveway Restoration
1	EA	Driveway Restoration, Gravel

***Division II of the Troy With Mosher & Farnham Drain is approximately 1.45 miles and is comprised of open channel, with an average depth of 14-feet and average bottom width of 3-feet, and 24-inch and 36-inch diameter, reinforced concrete pipe storm sewer. The following items will be required and a contract let for the same:***

#### **Open Channel Drain Construction**

1	LS	Mobilization
1	LS	Traffic Control
1	LS	Utility Coordination & Protection
1,890	LF	Clearing, Grubbing and Snagging
680	LF	Sediment Removal
2,150	LF	Open Channel Seeding
2,650	LF	Seeding – Special

#### **Drain Crossings**

Station 89+55, Private Crossing
Place 25 LF 59" x 81" CMP Arch
Station 90+50, 92 <sup>nd</sup> St (Paved)
Place 64 LF 72" RCP

#### **Enclosed Drain Construction**

10	EA	Lateral Connection
284	LF	Storm Sewer, 36-inch RCP W/ Underdrain
2,221	LF	Storm Sewer, 36-inch RCP
1,207	LF	Storm Sewer, 24-inch RCP W/ Underdrain
309	LF	Storm Sewer, 24-inch RCP
15	LF	Storm Sewer, 12-inch RCP
5	EA	Catch Basin, 4-foot diameter
2	EA	Flared End Section, 36-inch RCP
1	EA	Flared End Section W/ Grate, 36-inch RCP
1	EA	Flared End Section, 72-inch RCP
3	EA	24-inch x 36-inch Inlet Tee
1	EA	24-inch x 24-inch Inlet Tee
4	EA	Storm Manhole, 4-foot diameter
8	EA	Structure Marker Post
2	EA	Core & Grout, 12-inch
3	EA	Bulkhead, 12-inch

#### **Soil Erosion and Sedimentation Control**

1	LS	Soil Erosion and Sedimentation Control
1	EA	Outfall Stabilization
205	SY	Riprap End Treatment, MDOT Plain
1	EA	Private Crossing Restoration
1	EA	Road Restoration
1	EA	Armored Spillway
1	EA	Driveway Restoration, Gravel

This Notice of Letting, the plans, specifications and bid proposal shall be considered a part of the

Contract. The Contract will be let in accordance with the Contract Documents now on file at Kent County Drain Commissioner's Office and available to interested parties. Bids will be made and received in accordance with these documents. Bidding Documents, including plans and specifications, are available electronically, free of charge, upon request by contacting Kyle Visker, P.E., of Land & Resource Engineering via email at [visker@lremi.com](mailto:visker@lremi.com) or telephone 616-301-7888.

Copies of Bidding Documents may only be obtained from Land & Resource Engineering at 2121 3 Mile Road NW, Walker, MI 49544 upon payment of a \$35.00 non-refundable deposit. An additional non-refundable charge of \$15 will be required for sending out Bidding Documents.

A security deposit in the amount of 5% of the total bid shall be submitted in the form of a cashier's check, money order, certified check or bidders bond shall be submitted with any bids. No cash will be permitted. The security deposits of all unsuccessful bidders shall be returned after the Contract is awarded.

**A mandatory pre-bid meeting will be held at 9 am on Friday, the 2<sup>nd</sup> day of April at the intersection of 92<sup>nd</sup> Avenue and Patterson Avenue in Caledonia, Michigan. The Engineer will be present to discuss the project. Prospective bidders are required to attend and participate in the conference. All bidders must sign in by name of attendee and business represented. Only bids from bidders in attendance at the pre-bid conference will be opened. All others will be considered non-responsive.**

The Contract will be awarded to the lowest responsive and responsible bidder giving adequate security for the performance of the work and meeting all conditions represented in the Instructions to Bidders. The Contract completion date and the terms of payment will be announced at the time and place of letting. If no satisfactory bids are received, we reserve the right to reject any and all bids and to adjourn to a time and location as we shall announce.

The following is a description of the several tracts or parcels of lands constituting the Special Assessment District of the Troy With Mosher & Farnham Drain, as well as a list of any county, township, city, village to be assessed at large:

**Caledonia Township, T5N, R10W:**

Section 17 – The West 100 feet of the South 200 feet of the Southwest 1/4.

Section 18 – The South 1,700 feet of the Southeast 1/4. The South 2,300 feet of the Southwest 1/4.

Section 19 – All.

Section 20 – The West 1,300 feet of the Northwest 1/4. The West 1,700 feet of the Southwest 1/4.

Section 30 – The North 1/2. The North 1,700 feet of the South 1/2.

**Gaines Township, T5N, R11W:**


Section 13 – The East 800 feet of the South 1,100 feet of the Southeast 1/4.

Section 24 – The East 1,000 feet of the Northeast 1/4. The East 1,300 feet of the Northeast 1/4 of the Southeast 1/4. The South 1/2 of the Southeast corner. The South 800 feet of the Southwest 1/4 of the Southwest 1/4.

Section 25 – The East 1,600 feet of the Northeast 1/4. The East 1,100 feet of the North 1,700 feet of the Southeast 1/4.

**At Large: Gaines Township, Caledonia Township and Kent County at large for benefits to county roads.**

Dated: 3/29/2021



Kenneth J Yonker  
Kent County Drain Commissioner